

GENERAL NOTES

1. This drawing is not to be scaled.

2. All dimensions shown are in millimeters, and do not take into account applied finishes, unless specifically indicated otherwise. 3. Any omissions or discrepancies found shall be reported to the Architect immediately.

4. This drawing is to be read in conjunction with the relevant sections of the specification, schedules or bill of quantities. 5. The contractor shall submit full shop/setout drawings for approval (based on site dimensions) prior to the commencement of any site works, or placing of any orders for the manufacture of any fittings, fixtures or components shown.

REVISIONS

No	Date	Description	Rev By
А	Nov 23	Line of fire resisting structure updated.	DS
		Partitions/floors etc updated to latest plans.	

Additional roof insulation Existing paint finish to be removed from interior plasterwork and ceiling finish checked for level. A section of ceiling is to be carefully removed to check existing construction with Ty-Mawr's technical department to confirm that the following specification is suitable.

Finish: Roof/ceiling finish to be lined with Ty-Mawr's internal insulation system consisting of: —60mm thick 'Homatherm ID-Q11' woodfibre board mechanically fixed to the ceiling with insulated fixings according to Ty-Mawr's recommendations. Internal finish of 1 coat 3mm superfine plaster finish on 1 coat fine hemp top coat on 1 coat fine hemp plaster with mesh.

Paint finish to be vapour permeable (Internal Silicate Paint/Ty-Mawr limewash/ Clay paint or Ecosphere) available from Ty-Mawr

Any areas of wall which are uneven to be plastered with levelling coat of Ty—Mawr's hydraulic lime plaster approx 15mm thick

External walls lined with Ty-Mawr's internal wall insulation system consisting of: 40mm thick 'Homatherm ID-Q11' woodfibre board fixed to walls with 'Adhere Vit' adhesive and mechanically fixed with insulated fixings according to Ty-Mawr's recommendations. Internal finish of 1 coat 3mm superfine plaster finish

on 1 coat fine hemp top coat on 1 coat fine hemp plaster with mesh. Paint finish to be vapour permeable (Internal Silicate Paint/Ty—Mawr limewash/ Clay paint or Ecosphere) available from Ty—Maw

Steel beams under gable wall to be positioned as high as possible.

Detail to structural engineers specification. Beams to be encased in 2 layers of 12.5 mm Gyproc Fireline plasterboard with taped and staggered joints and skim finish, to give equivalent to 30mins fire resistance.

Steel beam to structural engineers specification. Level determined by eaves detail. Beam to be encased in 2 layers of 12.5 mm Gyproc Fireline plasterboard with taped and staggered joints and skim finish, to give equivalent to 30mins fire resistance.

Carefully take up existing stone flooring and store for reuse elsewhere. Reclaimed or new stone flags (to approval) laid on Ty—Mawr's 'sublime' insulated floor system consisting of: 100mm limecrete slab with 40mm cork board edge insulation to perimeter laid on clip rail underfloor heating pipe layout to approval.

on geogrid layer laid on 280mm thick compacted Glapor SG600 RFG.

All work to be carried out according to Ty-Mawr's specification.

Reclaimed or new stone flags (to approval) laid on Ty—Mawr's insulated floor system consisting of: 100mm limecrete slab with 40mm cork board edge insulation to perimeter laid on clip rail underfloor

on 100mm corkboard insulation available from Ty-Mawr. on beam and block flooring to structural engineers specification. Junction between suspended flooring and solid flooring to incorporate movement joint. All work to be carried out according to Ty-Mawr's specification.



Godwin Austen Johnson (GAJ) UK Ltd Chartered Architects

19 York Street Stourport-on-Severn Worcestershire DY13 9EH

PROJECT

T +44 1299 824567

E post@gajuk.com

W www.gaj-uk.com

Alterations to Kimberley House Severnside South, Bewdley, Worcestershire. DY12 2DX

CLIENT

Mr. & Mrs. R. Bailey

This drawing, the designs and details shown are the copyright of Godwin Austen Johnson (GAJ) UK Limited and shall not be copied or reproduced in any form without their written consent.

Drawing Title Proposed Section C-C

F			R	IB/	/ /# /	
Issue Status Listed Blo	Regs	\$		Rev A		
Project No 1689	Drawing No 07					
Checked • -		Scale	o	1:25 @ A1		
Drawn ∘ G	Date	o	03.10	2022		

Chartered Practice